

Historic, Archive Document

Do not assume content reflects current scientific knowledge, policies, or practices.

Reserve
aTC424
.W6F586

FLOODPLAIN MANAGEMENT STUDY PINE RIVER WAUSHARA COUNTY, WISCONSIN



**Prepared by:
United States Department of Agriculture
Soil Conservation Service
Madison, Wisconsin**

**In cooperation with:
Waushara County, Wisconsin
and the
Wisconsin Department of Natural Resources**

April 1989

AD-33 Bookplate
(1-68)

NATIONAL

**A
G
R
I
C
U
L
T
U
R
A
L**



LIBRARY



United States
Department of
Agriculture

Soil
Conservation
Service

6515 Watts Road, Suite 200
Madison, WI 53719-2726

May 1, 1989

National Agricultural Library
Joseph H. Howard, Director
Beltsville, Maryland 20705

Dear Sir:

Enclosed is a copy of the recently completed "Floodplain Management Study Report for Pine River, Waushara County, Wisconsin." This study was made at the request of the Waushara County through the Wisconsin Department of Natural Resources in accordance with the Department's joint agreement with the Soil Conservation Service.

This study was carried out in accordance with Federal Level Recommendation 3 of a "Unified National Program for Floodplain Management," and Section 6 of Public Law 83-566. The principles contained in Executive Order 11988, Floodplain Management, are addressed in this part. The purpose of the study is to make flood hazard and land use information available to the local government and citizens. It's intent is to promote proper land use.

The Soil Conservation Service's objective in developing this technical data is to help reduce present and potential flood damages through wise use of floodplain lands thereby improving the health, safety, economy, and the environmental condition of the county.

Sincerely,


for Charles R. Cobb
DUANE JOHNSON
State Conservationist

Enclosure



The Soil Conservation Service
is an agency of the
Department of Agriculture

	<u>Page</u>
Introduction	1
Study Area Description	1
Natural and Beneficial Floodplain Values	2
Flooding Problems	3
Existing Floodplain Management	4
Alternatives for Mitigating Flood Damages to Existing and Future Development	4
Vicinity Map	5



Appendices

- A. Flood Boundary Maps
- B. Flood Profiles
- C. Typical Sections
- D. Elevation Reference Marks
- E. Tabulation of Water Surface Elevations Discharges and Floodway
Tables
- F. Investigations and Analysis
- G. Glossary
- H. Bibliography

1991 8 5 370

Waushara County Floodplain Management Study
Pine River

901696

Introduction

The purpose of this study is to define the flood characteristics of the Pine River from the Village of Poy Sippi to the junction with the outlet of Wilson Lake, Carpenter Creek from its junction to County Highway NN, Little Silver Creek from its junction to the center of Sec. 9, T. 20 N., R. 12 E., and Popple Creek from its junction to 26th Road. Waushara County requested the study through the Wisconsin Department of Natural Resources (DNR).

This report is prepared for use by the county in planning the use and regulation of the floodplains of the Pine River, Carpenter, Little Silver and Popple Creeks.

The 100-year floodplain combined with the dam failure analysis has been delineated on the photomaps. The high water elevations and floodplain delineations are based on 5-year projected land use of the watershed. The existing stream, floodplain, and road crossings were utilized for the hydraulic analysis.

The Soil Conservation Service carries out floodplain management studies in accordance with Federal Level Recommendation 3 of "A Unified National Program for Floodplain Management," and Section 6 of Public Law 83-566. The principles contained in Executive Order 11988, Floodplain Management, are addressed in this part.

In Wisconsin, the Soil Conservation Service coordinates floodplain management studies with the Wisconsin DNR, through a joint coordination agreement entered into in October 1978. The Wisconsin Water Resources Act (Chapter 614, Laws of Wisconsin, 1965) authorizes the DNR, Division of Enforcement, to establish and upgrade minimum standards for floodplain regulations.

Study Area Description

Pine River is located in east central Waushara County. Waushara County is located in central Wisconsin. The study area consists of the floodplain adjacent to 17 miles of the Pine River.

The downstream study limit is the east section line of Sec. 7, T. 19 N., R. 12 E. The upstream study limit is the west section line of Sec. 26, T. 20 N., R. 11 E. Carpenter Creek was studied for a distance of 0.76 miles from its confluence to just above County Highway NN. Little Silver Creek was studied a distance of 1.84 miles from its confluence to a point near the north quarter corner of Sec. 9, T. 19 N., R. 12 E. or the corner of E, H and Beaver Avenue. Popple Creek was studied for a distance of 0.43 miles from its confluence to just above 26th Road.

A summary of the directly contributing drainage area followed by the noncontributing areas such as potholes and lake are as follows:

Pine River:	Contributing + Noncontributing =				Total	
Upper study limit	30	sq.mi.	23.0	sq.mi.	53.0	sq.mi.
Saxville Dam	34.2	sq.mi.	23.4	sq.mi.	57.6	sq.mi.
Pine River Dam	40.0	sq.mi.	24.7	sq.mi.	64.7	sq.mi.
Below confluence of Carpenter Creek	53.11	sq.mi.	25.3	sq.mi.	78.41	sq.mi.
Below confluence of Little Silver Creek	63.25	sq.mi.	29.1	sq.mi.	92.35	sq.mi.
Poy Sippi	70.3	sq.mi.	29.1	sq.mi.	99.4	sq.mi.
Lower study limit	70.7	sq.mi.	29.1	sq.mi.	99.8	sq.mi.
Carpenter Creek						
Upper study limit	12.1	sq.mi.	0.6	sq.mi.	12.7	sq.mi.
At confluence	12.4	sq.mi.	0.6	sq.mi.	13.0	sq.mi.
Little Silver Creek						
Upper study limit	8.36	sq.mi.	0.18	sq.mi.	8.54	sq.mi.
Confluence	10.14	sq.mi.	4.06	sq.mi.	14.2	sq.mi.
Popple Creek						
Upper study limit	2.05	sq.mi.	0.46	sq.mi.	2.51	sq.mi.
Confluence	3.17	sq.mi.	0.46	sq.mi.	3.63	sq.mi.

The Pine River is in Hydrologic Unit 04030202180.

The climate is typically continental. January temperatures average 19 degrees F. July, the warmest month, has an average temperature of 73 degrees F. The average maximum for July is 85 degrees F with the average minimum at 61 degrees F. Precipitation averages 29 inches per year (8).

The soils of the watershed consist mostly of Plainfield-Okee-Richford association, described in the General Soil Map section of the Waushara County Soil Survey, which are strongly sloping to steep, somewhat excessively drained and excessively drained, sandy soils on moraines. The lowlands, east of Wild Rose of Little Silver Creek and upper Popple Creek are of the Kingsville-Mechan association, whose soils are nearly level and gently sloping, poorly drained and somewhat poorly drained, sandy, soils on outwash plains. The lowlands of Carpenter Creek are made up of Houghton-Adrian-Willette association soils which are nearly level, very poorly drained, muck soils on outwash plains, lake plains, or moraines.

Natural and Beneficial Floodplain Values

The Pine River is a clear hardwater trout stream flowing through much of northern Waushara County. The portion of the river in the study area is generally referred to as the Lower Pine River. It is a class I trout stream down to 8 miles above the Poy Sippi millpond where it is a class II trout stream. Brown trout dominate the fishery of the Lower Pine.

The lower parts of three other trout streams are also in the study area. Carpenter Creek enters the Lower Pine approximately one mile east of the Village of Pine River. This is a class II trout stream containing mostly brown trout.

Popple Creek enters the Lower Pine just south of Saxville. It originates as an outlet to Baitenger Lake. It is a class I trout stream containing brown trout. Little Silver Creek flows east into the Lower Pine about 1-1/2 miles east of the Village of Pine River. It is a class I trout stream containing brown and brook trout.

Three millponds are located in the study area. The Saxville millpond (13.3 ac.) has a maximum depth of 3.5 feet. It contains largemouth bass, bluegill, and green sunfish. The Pine River millpond (28.3 ac.) has a maximum depth of 4 feet. It does contain some trout. The Poy Sippi millpond (57.3 ac.) has a maximum depth of 7 feet. White sucker is the dominant fish species. Other species present include the northern pike, largemouth bass, black bullhead, and redhorse.

The floodplain consists primarily of lowland tree and shrub species including willow, boxelder, ash, dogwood, and alder. The uplands surrounding the floodplain consist of woodlands of red pine, jack pine, and oak along with some cropland and idle grasslands. Because of the variety of vegetation cover types, much habitat is provided for a variety of wildlife species including white-tailed deer, ruffed grouse, cottontail rabbits, gray squirrels, red fox, mink, otter muskrats, beaver, and numerous birds. Waterfowl and shorebirds are found in the millponds.

Along with providing important wildlife habitat, the undeveloped floodplain provides a buffer to help filter runoff and provides a natural storage area for large amounts of floodwater during peak flows.

There are no known threatened or endangered species in the study area. There are no sites on the National Register of Historic Places. None of the streams are listed as being eligible for the National Wild and Scenic Rivers program. There is no prime farmland.

Flooding Problems

No significant flash flooding occurs on the Pine River system. The numerous flowages, swamps, depressions, lakes and sandy soils store and release the water over a prolonged period. The increase in flow is handled by removing stoplogs or panels from the dams.


The Pine River dam washed out in July 1969 by overtopping of the embankment adjacent to the spillway. This was caused by a series of events rather than a flash flood. The spring of 1969 was wet with 3.77 inches of rain in April, 5.82 inches in May, and 6.20 inches in June. A large portion (4.24 inches) of the June rainfall occurred during the last week of June (25th to 30th). This 15.79 inches of rainfall, especially the last 4 inches, would have filled the depressional areas and swamps creating a wet hydrologic condition such that the 1.8 inches of rainfall on July 4th was mostly runoff. The excess water overtopped the Saxville dam by 5 to 6 inches. Panels were removed from the spillway to release the water and protect the dam. Downstream, the Pine River Dam failed and there was some concern for the dam structure at Poy Sippi.

Existing Floodplain Management

Wauashara County adapted a floodplain ordinance in 1986. The ordinance has been approved by the Wisconsin Department of Natural Resources. The county is ineligible for the National Flood Insurance Program and cannot receive disaster assistance or make federally insured loans in flood hazard areas. The county has submitted a letter to Federal Emergency Management Agency requesting participation in the program.

Alternatives for Mitigating Flood Damages to Existing and Future Developments


- A. Incorporate the floodplain maps from this study into a floodplain ordinance and provide enforcement.
- B. Apply existing standards set forth in the county's subdivision control ordinance to regulate development in unsuitable areas and minimize erosion and diffused surface water runoff within the watershed.
- C. Protect two buildings that are in the floodplain by floodproofing or removing from the floodplain.
- D. Prepare a management plan for flowage operation on the river system. This plan could consist of monitoring the hydrologic condition of the watershed and operating outlet works accordingly. The dam operator should have a standard operating procedure that includes notifying the downstream dam operators of operation changes.
- E. Automate the outlet works utilizing the existing control equipment for the hydroelectric generators at Pine River and Poy Sippi.



Appendix A

FLOOD BOUNDARY MAPS






- LEGEND
- TOWN
 - ④⑨ STATE HIGHWAY
 - ⓔ COUNTY HIGHWAY
 - DRAINAGE
 - - - RANGE AND TOWNSHIP LINES
 - STREAM REACH STUDIED
 - 1 SHEET COVERAGE




VICINITY MAP

INDEX TO MAP SHEETS
WAUSHARA COUNTY
FLOOD PLAIN MANAGEMENT STUDY
 WAUSHARA COUNTY, WISCONSIN



SOURCE:
 BASE FROM 1984 WAUSHARA
 COUNTY GENERAL HIGHWAY
 MAP AND DATA FROM SCS
 FIELD PERSONNEL





100 Year Flood or Breach Inundation
Whichever is Greatest.

768.4 Flood Elevation

LEGEND

RM 2 Reference Bench Marks


Stream Channel

Floodway Limit



Valley Section Location

DUE TO INHERENT AERIAL PHOTOGRAPHIC DISPLACEMENT,
THE PHOTOGRAPHIC IMAGE MAY VARY FROM TRUE GROUND LOCATION




1977 Photography

U.S. DEPARTMENT OF AGRICULTURE
SOIL CONSERVATION SERVICE
WAUSHARA COUNTY
FLOOD PLAIN MANAGEMENT STUDY AREA
WAUSHARA COUNTY, WISCONSIN


FLOOD HAZARD AREA




PINE RIVER





LEGEND

 100 Year Flood or Breach Inundation
Whichever Is Greatest.
768.4 Flood Elevation

 **RM 2** Reference Bench Marks
 Stream Channel
 Floodway Limit

 **A** Valley Section Location

SCALE
0 400 800 FEET
0 100 200 METERS
APPROXIMATE

DUE TO INHERENT AERIAL PHOTOGRAPHIC DISPLACEMENT,
THE PHOTOGRAPHIC IMAGE MAY VARY FROM TRUE GROUND LOCATION.

1977 Photography



U.S. DEPARTMENT OF AGRICULTURE
SOIL CONSERVATION SERVICE
WAUSHARA COUNTY
FLOOD PLAIN MANAGEMENT STUDY AREA
WAUSHARA COUNTY, WISCONSIN

FLOOD HAZARD AREA

PINE RIVER


1:25,000 SCALE, PHOTOGRAPHIC CONTROL, 7/11/87, 1/1/87



LEGEND

- 100 Year Flood or Breach Inundation Whichever Is Greatest.
- 768.4** Flood Elevation
- RM 2** Reference Bench Marks
- Stream Channel
- Floodway Limit

- Valley Section Location




1977 Photography

1977 Photography

U.S. DEPARTMENT OF AGRICULTURE
SOIL CONSERVATION SERVICE
WAUSHARA COUNTY
FLOOD PLAIN MANAGEMENT STUDY AREA
WAUSHARA COUNTY, WISCONSIN


FLOOD HAZARD AREA

PINE RIVER








LEGEND

 100 Year Flood or Breach Inundation
Whichever Is Greatest.

768.4 Flood Elevation


 **RM 2** Reference Bench Marks

 Stream Channel

 Floodway Limit

 Valley Section Location

DUE TO INHERENT AERIAL PHOTOGRAPHIC DISPLACEMENT,
THE PHOTOGRAPHIC IMAGE MAY VARY FROM TRUE GROUND LOCATION

SCALE 
0 400 800 FEET
0 100 200 METERS
APPROXIMATE

1977 Photography




U.S. DEPARTMENT OF AGRICULTURE
SOIL CONSERVATION SERVICE
WAUSHARA COUNTY
FLOOD PLAIN MANAGEMENT STUDY AREA
WAUSHARA COUNTY, WISCONSIN

FLOOD HAZARD AREA

PINE RIVER

SHEET 4 OF 11

DECEMBER 1988 1004120





LEGEND

- 100 Year Flood or Breach Inundation
Whichever Is Greatest.
- 768.4** Flood Elevation
- RM 2** Reference Bench Marks
- Stream Channel
- Floodway Limit

- Valley Section Location

SCALE 0 400 800 FEET
0 100 200 METERS
APPROXIMATE

DUO TO INHERENT AERIAL PHOTOGRAPHIC DISPLACEMENT,
THE PHOTOGRAPHIC IMAGE MAY VARY FROM TRUE GROUND LOCATION

1977 Photography



U.S. DEPARTMENT OF AGRICULTURE
SOIL CONSERVATION SERVICE
WAUSHARA COUNTY
FLOOD PLAIN MANAGEMENT STUDY AREA
WAUSHARA COUNTY, WISCONSIN

FLOOD HAZARD AREA

LITTLE SILVER CREEK





**PINE
RIVER**

MATCH TO SHEET 7
805.3

TURBINE
OUTLET

PINE

RIVER
CARPENTER

CREEK

COURT

2874

— 2 —

T 20 N

AM 2

Reference Bench Marks

Stream Channel

Floodway Limit

A

Valley Section Location

DUE TO INHERENT AERIAL PHOTOGRAPHIC DISPLACEMENT,
THE PHOTOGRAPHIC IMAGE MAY VARY FROM TRUE GROUND LOCATION

1977 Photography

0 400 800 FEET

SCALE 0 100 200 METERS

APPROXIMATE

FLOOD HAZARD AREA

PINE RIVER AND CARPENTER CREEK

U.S. DEPARTMENT OF AGRICULTURE
SOIL CONSERVATION SERVICE
WAUSHARA COUNTY

FLOOD PLAIN MANAGEMENT STUDY AREA
WAUSHARA COUNTY, WISCONSIN




LEGEND

- 100 Year Flood or Breach Inundation
Whichever Is Greatest.
- 768.4** Flood Elevation

- RM 2** Reference Bench Marks
- Stream Channel
- Floodway Limit

- Valley Section Location

DUE TO INHERENT AERIAL PHOTOGRAPHIC DISPLACEMENT,
THE PHOTOGRAPHIC IMAGE MAY VARY FROM TRUE GROUND LOCATION.




1977 Photography



U.S. DEPARTMENT OF AGRICULTURE
SOIL CONSERVATION SERVICE
WAUSHARA COUNTY
FLOOD PLAIN MANAGEMENT STUDY AREA
WAUSHARA COUNTY, WISCONSIN

FLOOD HAZARD AREA

PINE RIVER



100-YEAR FLOOD HAZARD AREA MAP
DECEMBER 1988 1004120




LEGEND

- 100 Year Flood or Breach Inundation
Whichever Is Greatest.
- 768.4** Flood Elevation
- RM 2 Reference Bench Marks
- Stream Channel
- Floodway Limit

- Valley Section Location

DUE TO INHERENT AERIAL PHOTOGRAPHIC DISPLACEMENT,
THE PHOTOGRAPHIC IMAGE MAY VARY FROM TRUE GROUND LOCATION



1977 Photography



U.S. DEPARTMENT OF AGRICULTURE
SOIL CONSERVATION SERVICE
WAUSHARA COUNTY
FLOOD PLAIN MANAGEMENT STUDY AREA
WAUSHARA COUNTY, WISCONSIN


SHEET 8 OF 11

FLOOD HAZARD AREA

PINE RIVER

R 11 E

MATCH TO SHEET 10




LEGEND

- 100 Year Flood or Breach Inundation Whichever Is Greatest.
- 768.4 Flood Elevation
- RM 2 Reference Bench Marks
- Stream Channel
- Floodway Limit

- Valley Section Location

DUE TO INHERENT AERIAL PHOTOGRAPHIC DISPLACEMENT, THE PHOTOGRAPHIC IMAGE MAY VARY FROM TRUE GROUND LOCATION





1977 Photography

U.S. DEPARTMENT OF AGRICULTURE
SOIL CONSERVATION SERVICE
WAUSHARA COUNTY
FLOOD PLAIN MANAGEMENT STUDY AREA
WAUSHARA COUNTY, WISCONSIN

FLOOD HAZARD AREA
PINE RIVER AND POPPLE CREEK


SHEET 9 OF 11






100 Year Flood or Breach Inundation
Whichever Is Greatest.


768.4 Flood Elevation




RM 2 Reference Bench Marks



Stream Channel




Floodway Limit




Valley Section Location

DUE TO INHERENT AERIAL PHOTOGRAPHIC DISPLACEMENT,
THE PHOTOGRAPHIC IMAGE MAY VARY FROM TRUE GROUND LOCATION

SCALE 
0 400 800 FEET
0 100 200 METERS
APPROXIMATE

1977 Photography



U.S. DEPARTMENT OF AGRICULTURE
SOIL CONSERVATION SERVICE
WAUSHARA COUNTY
FLOOD PLAIN MANAGEMENT STUDY AREA
WAUSHARA COUNTY, WISCONSIN

FLOOD HAZARD AREA

PINE RIVER

SHEET 10 OF 11

DECEMBER 1988 1004120

DATA COURTESY OF USGS, 1977, 1978, 1979



LEGEND

- 100 Year Flood or Breach Inundation
Whichever Is Greatest.
- Stream Channel
- Floodway Limit
- Valley Section Location
- RM 2 Reference Bench Marks
- Flood Elevation

Valley Section Location



DUE TO INHERENT AERIAL PHOTOGRAPHIC DISPLACEMENT,
THE PHOTOGRAPHIC IMAGE MAY VARY FROM TRUE GROUND LOCATION

1977 Photography



U.S. DEPARTMENT OF AGRICULTURE
SOIL CONSERVATION SERVICE
WAUSHARA COUNTY
FLOOD PLAIN MANAGEMENT STUDY AREA
WAUSHARA COUNTY, WISCONSIN

FLOOD HAZARD AREA

PINE RIVER

SHEET 11 OF 11


DECEMBER 1988 1004120




Appendix B

FLOOD PROFILES








PINE RIVER
VAUSHARA COUNTY
FLOODPLAIN MANAGEMENT STUDY
VAUSHARA COUNTY, WISCONSIN


U.S. DEPARTMENT OF AGRICULTURE
SOIL CONSERVATION SERVICE

Designed by	J. MILLER	Scale	1"=20'
Drawn by	B. JAMES	Date	1/28
Checked by		Sheet No.	2
Engineer		Project No.	72



LEGEND

- - - 100 YEAR FLOOD OR DAM BREACH
- STREAM BED




CROSS SECTION LOCATION


- BRIDGE FLOOR
- LOW POINT IN ROAD
- LOW CHORD

PINE RIVER
WAUSHARA COUNTY
FLOODPLAIN MANAGEMENT STUDY
WAUSHARA COUNTY, WISCONSIN

U.S. DEPARTMENT OF AGRICULTURE
SOIL CONSERVATION SERVICE

Designed by	J. HILGEM	Date	1/09	Approved by		Title	
Drawn by	B. JENSEN	Date	1/09	Checked by		Sheet	5
Field notes		Date		Reviewed by		Drawn by	22
Checked by		Date					






PINE RIVER
WAUSHARA COUNTY
FLOODPLAIN MANAGEMENT STUDY
WAUSHARA COUNTY, WISCONSIN

U.S. DEPARTMENT OF AGRICULTURE
SOIL CONSERVATION SERVICE


Designed by	J. M. Loomis	Date	1/28
Checked by	B. J. Loomis	Date	1/28
Drawn by		Date	
Reviewed by		Date	
Approved by		Date	
Project No.	5	Sheet No.	11
Project Name		Project Location	





PINE RIVER
WAUSHARA COUNTY
FLOODPLAIN MANAGEMENT STUDY
WAUSHARA COUNTY, WISCONSIN


U.S. DEPARTMENT OF AGRICULTURE
SOIL CONSERVATION SERVICE

Designed	By	Checked	By	Drawn	By	Scale	Sheet No.	Total Sheets
	J. MILLER		1/25		1/25		5	12
	B. JAMES		1/25		1/25			









LEGEND

--- 100 YEAR FLOOD
OR DAM BREACH
— STREAM BED

CROSS SECTION LOCATION

BRIDGE FLOOR

LOW POINT IN ROAD


LOW CHORD





PINE RIVER
VAUSHARA COUNTY
FLOODPLAIN MANAGEMENT STUDY
VAUSHARA COUNTY, WISCONSIN


U.S. DEPARTMENT OF AGRICULTURE
SOIL CONSERVATION SERVICE


Prepared by	J. MILLER	Date	1/68
Drawn by	B. JENSEN	Checked by	
Reviewed by		Approved by	
		Title	
		Scale	
		Sheet	10
		Project	












PINE RIVER
 WAUSHARA COUNTY
 FLOODPLAIN MANAGEMENT STUDY
 WAUSHARA COUNTY, WISCONSIN
 U.S. DEPARTMENT OF AGRICULTURE
 SOIL CONSERVATION SERVICE


Designed by	J. MILLER	Date	1/25	Approved by		
Drawn	S. J. M. Co.	Date	1/28	Title		
Checked				Letter		
Recorded				Sheet	18	of 21
				Drawing #		





PINE RIVER
WAUSHARA COUNTY
FLOODPLAIN MANAGEMENT STUDY
WAUSHARA COUNTY, WISCONSIN

U.S. DEPARTMENT OF AGRICULTURE
SOIL CONSERVATION SERVICE

Revised	Drawn	Checked	Approved by	Title	Scale	Sheet	Project No.
	J. MILLER				1/20	17	
	B. JENSEN				1/20	18	
						19	
						20	
						21	
						22	









**LITTLE SILVER CREEK
WAUSHARA COUNTY
FLOODPLAIN MANAGEMENT STUDY
WAUSHARA COUNTY, WISCONSIN**

**U.S. DEPARTMENT OF AGRICULTURE
SOIL CONSERVATION SERVICE**

Designed by	J. MILLER	Date	1/55
Drawn by	B. JENSEN	Date	1/55
Checked by		Date	
Approved by		Date	
Sheet No.	20	Project No.	







Appendix C

TYPICAL SECTIONS







LEGEND

- 100-YEAR FLOOD
- GROUND LINE

TYPICAL CROSS SECTION

**LITTLE SILVER CREEK
WAUSHARA COUNTY
FLOODPLAIN MANAGEMENT STUDY
WAUSHARA COUNTY, WISCONSIN**

**U.S. DEPARTMENT OF AGRICULTURE
SOIL CONSERVATION SERVICE**

Designed	J. MILLIGAN	1/86	Checked	J. MILLIGAN	1/86
Drawn	M. MORRIS	1/86	Reviewed	J. MILLIGAN	1/86
Scale	1" = 100'		Scale	1" = 100'	
Sheet	1 of 1		Sheet	1 of 1	

ELEVATIONS IN FEET (MSL)

860

850

840

830

DISTANCE IN FEET
CROSS SECTION "G"

500

400

300

200

100

0

LEGEND

100-YEAR FLOOD
GROUND LINE

TYPICAL CROSS SECTION

POPPLE CREEK
WAUSHARA COUNTY
FLOODPLAIN MANAGEMENT STUDY
WAUSHARA COUNTY, WISCONSIN
U. S. DEPARTMENT OF AGRICULTURE
SOIL CONSERVATION SERVICE

Designed	J. MILLIGAN	1/86	Applied by	J. MILLIGAN	1/86
Drawn	M. MORRIS	1/86	Checked	M. MORRIS	1/86
Traced	J. MILLIGAN	1/86	Reviewed	J. MILLIGAN	1/86
Scale			Sheet		
Project			Drawn by		
Drawn by			Checked		
Drawn by			Reviewed		

ELEVATIONS IN FEET (MSL)

805
800
795
790
785

0

100

200

300

400

DISTANCE IN FEET
CROSS SECTION "Y"


LEGEND

- GROUND LINE
- 100 YR. FLOOD
- DAM BREACH WATER SURFACE

TYPICAL CROSS SECTION

PINE RIVER
WAUSHARA COUNTY
FLOODPLAIN MANAGEMENT STUDY
WAUSHARA COUNTY, WISCONSIN
U. S. DEPARTMENT OF AGRICULTURE
SOIL CONSERVATION SERVICE

Designed	Date	Approved by	Title
Drawn	7-88		
Traced			
Checked			



ELEVATIONS IN FEET (MSL)

ELEVATIONS IN FEET (MSL)

810

800

790

780

820

810

800

790

0

100

200

300

400

100

200

300

DISTANCE IN FEET
CROSS SECTION C1

DISTANCE IN FEET
CROSS SECTION C2 50' SOUTH OF HIGHWAY NN

LEGEND

100-YEAR FLOOD
GROUND LINE

TYPICAL CROSS SECTION
500 600

CARPENTER CREEK
WAUSHARA COUNTY
FLOODPLAIN MANAGEMENT STUDY
WAUSHARA COUNTY, WISCONSIN
U.S. DEPARTMENT OF AGRICULTURE
SOIL CONSERVATION SERVICE

Designed By	J. MILLIGAN	Date	1/86
Checked By	M. MORRIS	Date	1/86
Drawn By	J. MILLIGAN	Date	1/86

Appendix D

ELEVATION REFERENCE MARKS



ELEVATION REFERENCE MARKS

<u>Reference Mark</u>	<u>Elev. (MSL)</u>	<u>Description</u>
1	778.066	USGS BM-M-98 1934. A standard brass disk located on the north end of the west headwall of north bridge of two concrete bridges located in the Village of Poy Sippi, Waushara County. State Highway 49.
2	789.54	TBM-1. A spike in south side of WPL pole No. 19-13-7.2 on south side of Liberty Street across from Poy Sippi grade school.
3	774.41	TBM-2. A spike in the west side of a 15-inch ash tree 100 feet north of North River Terrace on west side of ditch from north along west line of section 8.
4	782.10	UE-17. A spike in west side of power pole No. 35-7 in field on west side of river 30 feet east of cross section 6P(H).
5	803.24	UE-18. A spike on north side of power pole No. 844 on south side of CTH H at cross section 7P(I).
6	782.00	UE-16. A spike in power pole No. 36-16 on east side of Wisconsin Street, 400 feet south of intersection with Commercial Street.
7	792.62	UE-20. A spike on north side of power pole No. 38-19 on south side of CTH H at cross section 8P(J).
8	793.93	UE-21. A spike in north side of power pole No. 48/33. Approximately 200 feet west of 32nd Drive to south on south side of CTH H at cross section 9P(K).
9	786.96	UE-22. A spike in power pole No. 14/33. Located approximately 400 feet west of Beaver Road intersection with County Highway H. Pole is located on south side of CTH H.
10	785.30	UE-25. A spike in north side of power pole No. 37/31 at cross section 11P(M). Pole is on the south side of CTH H.
11	788.21	UE-26. A spike in north side of power pole No. 30/36. Pole is on the south side of CTH H at cross section 12P(N).
12	788.05	UE-27. A spike in power pole No. 15/37, with transformer, on south side of CTH H. Located at cross section 13P(O).
13	795.38	UE-28. A spike in west side of power pole No. 51/39 with wire crossing CTH H to north.

14	798.51	UE-29. A spike in power pole No. 35/47 on south side of CTH H at cross section 15P(Q).
15	792.73	UE-30. Top of the north end of the east headwall of the bridge on 28th Court crossing the Pine River. Located on the north line of Sec. 10, T. 19 N., R. 12 E. (town of Leon).
16	821.95	UE-36. A spike in north side of 48-inch oak tree. Located on the west side of 28th Court. Approximately 600 feet north of the intersection with Badger Road.
17	851.03	UE-37. A spike in west side of power pole. Located on east side of 28th Court. Approximately 100 feet north of hill top which is located in the NE 1/4, SW 1/4, Sec. 3, T. 19 N., R. 12 E.
18	809.13	UE-38. Top of steel reflector post on south side of Schroeder driveway and 100 feet west of 28th Court.
19	822.66	UE-39. Top of east end of 30-inch diameter corrugated metal pipe culvert under 28th Court. Located 600 feet north of the Sorenson farm buildings.
20	825.18	UE-40. Top of the ANR Pipe Line Co. gas riser (orange). Located on the north side of CTH NN at the intersection with 28th Court.
21	804.95	UE-41. Top of north end of 36-inch CMP carrying Carpenter Creek under CTH NN. Pipe is 15 feet east of a 10.5 x 7.1 foot corrugated metal pipe arch.
22	817.15	UE-42. A spike 3.5 feet above ground in west side of power pole No. 635. Located in NE corner of intersection of 28th Road and CTH NN.
23	810.94	UE-15. Top of south end of south wingwall on upstream side of the dam at Pine River.
24	821.67	UE-14. A spike in power pole No. 10. Located on the north side of CTH H in Pine River. Pole is approximately 750 feet west of the junction with CTH E.
25	833.06	UE-13. A spike in south side of power pole No. 22/0 on north side of CTH H across from Sorenson building.
26	825.15	UE-12. A spike on the south side of power pole No. 3/0 on north right-of-way of CTH H. Approximately 600 feet east of the intersection of 26th Road with CTH H.
27	855.92	UE-11. A spike on north side of power pole No. 39/26 on south side of CTH H at the junction with 26th Road.

28	861.91	UE-10. A spike in west side of power pole No. 37/32 on east side of 26th Road. Approximately 800 feet north of CTH H.
29	878.44	UE-9. Top of 3-foot diameter rock on north side of 26th Road about 600 feet down (south) of hill top.
30	877.97	UE-8. A spike in north side of power pole No. 22/43 on south side of 26th Road.
31	838.69	UE-6. Top of 5-inch square concrete post. Located on east side of 26th Road. Approximately 100 feet south of Edgar Fraeters buildings.
32	828.58	UE-5. A nail in the north side of power pole No. 20-12-32 8/24 on south side of 26th Road between 29P(AF) and 30P(AG).
33	827.65	UE-4. On "X" on a 24-inch diameter white pine stump 40 feet northwest of road to small bridge in NW 1/4 of NW 1/4 of Sec. 32, T. 20 N., R. 12 E.
34	868.17	UE-2. Top of 3-foot diameter granite rock on the east right-of-way of 26th Road at curve to the southeast.
35	888.64	UE-1. Top of a large granite rock on south side of 26th Road. Approximately 600 feet east of junction with CTH W.
36	835.06	USGS square, a chipped square at the downstream end of the top left abutment at the gates.
37	854.32	UE-51. Top of steel post with house No. 3081 on south side of intersection of Portage and Willow Streets.
38	834.83	UE-55. A large round granite rock with chipped west side, covered with green lichen. Reading was taken on highest point.
39	843.65	UE-59. Top of north end of 72-inch diameter corrugated metal culvert pipe on crossing above CTH A and below Lake Kristine dam.
40	847.86	UE-60. Spike on south side of power transformer pole 1200 feet west of intersection with CTH W. Sixty feet south of southwest corner of barn.
41	854.01	UE-61. Top of northeast corner of outlet structure for Lake Kristine.
42	845.62	UE-63. Top north end of east headwall of rock arch bridge at Ding Supper Club.

43	837.40	UE-64. Top of west end of highest rock in a rubble masonry check dam of south end of cross section 37P(AN).
44	865.44	UE-65. Top of a large granite rock located on the north side of Portage Road at cross section 42P(AR).
45	831.80	UE-66. Top of the north steel pier on the west side of the bridge on 24th Lane.
46	859.14	UE-67. Top of northeast headwall of CTH A bridge (level with road surface).
47	899.82	UE-70. A spike in north side of power pole No. 630. Located on south side of CTH A. Approximately 2000 feet west of the Pine River Bridge.
48	873.05	UE-71. Top of west 6x6 inch gate post with hinges. Located on the north side of CTH A near cross section AY.
49	860.19	UE-72. A spike on the east side of a 12-inch diameter ash tree that "Y"'s into two major trunks, approximately 6 feet north of the north river bank at cross section AY.
50	928.02	UE-73. Top pail handle knob on old hand pump faucet on north side of CTH A at top of hill.
51	899.46	UE-74. A spike in power pole on west side of driveway. Approximately 350 feet north of UE-73 (RM 50).
52	885.44	UE-75. Top of a 2-inch iron pipe on the north right-of-way of CTH A and along the west line of Sec. 26, T. 20 N., R. 11 E. Springwater Township.
53	866.23	UE-76. Top of first 1-inch diameter pipe south of the west edge of the bridge crossing the Pine River at the confluence with the Wilson Lake outlet.

Appendix E

TABULATION OF
WATER SURFACE ELEVATIONS
DISCHARGES
AND
FLOODWAY TABLES

Flooding Source		Discharge - Elevation							
Cross section	Distance ^{1/}	10-year		50-year		100-year		500-year	
		Q CFS	Elev. MSL	Q CFS	Elev. MSL	Q CFS	Elev. MSL	Q CFS	Elev. MSL
<u>PINE RIVER</u>									
A	0	920	764.4	1300	765.3	1450	765.7	1900	766.4
B	1920	920	766.1	1300	767.1	1450	767.4	1900	768.1
C	3040	920	767.0	1300	767.9	1450	768.3	1900	769.0
D	3320	895	767.1	1265	768.1	1412	768.5	1850	769.3
E	3625	400	767.7	580.0	768.6	644	769.0	709	769.6
	3730	STATE HIGHWAY 49							
F	3780	400	768.5	580.0	769.4	644	769.8	709	770.2
G	3940	400	768.5	580.0	769.4	644	769.8	709	770.2
	4040	POY SIPP DAM							
H	4880	895	774.3	1265	775.0	1412	775.5	1850	776.6
I	6560	895	774.4	1265	775.1	1412	775.6	1850	776.7
J	8440	895	774.8	1265	775.5	1412	775.9	1850	776.9
K	9720	895	775.4	1265	776.0	1412	776.3	1850	777.2
L	11650	871	776.2	1231	776.8	1373	777.1	1800	777.8
M	15090	871	779.1	1231	779.7	1373	779.8	1800	780.4
N	17370	871	780.3	1231	780.9	1373	781.1	1800	781.6
O	20870	871	782.0	1231	782.9	1373	783.1	1800	783.6
P	24510	870	784.5	1230	785.4	1380	785.6	1750	786.2
Q	26440	870	786.0	1230	786.8	1380	787.1	1750	787.7
R	28720	870	787.6	1230	788.7	1380	789.0	1750	789.8
S	29840	750	788.3	1061	789.4	1190	789.7	1540	790.5
	29860	28TH COURT							
T	29900	750	789.0	1061	789.6	1190	789.9	1540	790.7
U	30330	750	789.1	1061	789.8	1190	790.1	1540	790.9
V	32580	750	789.8	1061	790.4	1190	790.7	1540	791.3
W	35620	750	791.4	1061	792.1	1190	792.4	1540	793.1

^{1/} Distance in feet from downstream study limit.

U.S. DEPARTMENT OF AGRICULTURE
SOIL CONSERVATION SERVICE
PINE RIVER FLOODPLAIN MANAGEMENT STUDY
WAUSHARA COUNTY, WISCONSIN

DISCHARGE - ELEVATION DATA

PINE RIVER

TABLE 1

Flooding Source		Distance $\frac{1}{2}$	Discharge - Elevation									
Cross section	10-year		50-year		100-year		500-year		Elev. MSL			
	Q CFS		Elev. MSL	Q CFS	Elev. MSL	Q CFS	Elev. MSL	Q CFS			Elev. MSL	
PINE RIVER cont.												
X	37250	589	791.9	834	792.7	935	793.0	1210	793.7			
Y	40520	589	796.0	834	797.1	935	797.4	1210	798.3			
Z	41105	538	798.0	761	798.7	854	798.9	1105	799.7			
	41265	COUNTY TRUNK HIGHWAY E										
AA	41315	538	798.8	761	799.6	854	800.1	1105	801.7			
	41365	PINE RIVER DAM										
AB	42525	589	807.8	834	807.9	935	808.0	1210	808.2			
AC	43845	589	809.2	834	809.7	935	810.0	1210	810.5			
AD	47295	589	813.5	834	814.3	935	814.6	1210	815.1			
AE	51275	589	816.6	834	817.4	935	817.7	1210	818.2			
AF	53915	589	817.2	834	818.0	935	818.3	1210	818.9			
AG	57295	589	819.0	834	819.8	935	820.2	1210	820.8			
AH	57315	589	819.7	834	820.2	935	820.4	1210	820.8			
	57330	PRIVATE BRIDGE NO. 1										
AI	60650	589	821.2	834	822.0	935	822.3	1210	823.0			
AJ	62950	589	822.9	834	823.8	935	824.2	1210	824.9			
AK	64050	535	823.5	754	824.5	845	824.9	1100	825.7			
	64085	PRIVATE BRIDGE NO. 2										
AL	64115	535	824.2	754	824.8	845	825.1	1100	825.9			
AM	66215	535	825.6	754	826.4	845	826.7	1100	827.7			
	66265	COUNTY HIGHWAY W										
	66300	SAXVILLE DAM										
AN	67300	535	835.0	754	835.2	845	835.3	1100	835.4			
AO	68700	535	835.1	754	835.4	845	835.5	1100	835.6			
AP	70100	535	836.4	754	831.1	845	837.4	1100	837.8			
	70140	BRIDGE (PRIVATE)										

$\frac{1}{2}$ Distance in feet from downstream study limit.

U.S. DEPARTMENT OF AGRICULTURE
SOIL CONSERVATION SERVICE
PINE RIVER FLOODPLAIN MANAGEMENT STUDY
WAUSHARA COUNTY, WISCONSIN

TABLE 1

DISCHARGE - ELEVATION DATA

PINE RIVER

Flooding Source		Discharge - Elevation							
Cross section	Distance ^{1/}	10-year		50-year		100-year		500-year	
		Q CFS	Elev. MSL	Q CFS	Elev. MSL	Q CFS	Elev. MSL	Q CFS	Elev. MSL
<u>PINE RIVER cont.</u>									
AQ	70185	535	837.5	754	838.8	845	839.3	1100	840.8
AR	71345	535	846.9	754	847.8	845	848.1	1100	848.9
AS	72065	535	849.8	754	850.5	845	850.8	1100	851.5
AT	72115	24TH LANE							
AU	72155	535	850.6	754	852.4	845	852.4	1100	853.5
	72955	535	852.3	754	853.5	845	853.7	1100	854.6
	72995	COUNTY TRUNK HIGHWAY A							
AV	73030	535	852.4	754	854.1	845	854.6	1100	856.1
AW	73630	535	854.0	754	855.1	845	855.5	1100	856.7
AX	74950	510	855.7	719	856.6	806	857.0	1050	857.7
AY	82190	510	860.0	719	860.5	806	860.8	1050	861.2
AZ	88400	450	864.0	675	864.8	760	864.4	1000	865.5
	88420	PRIVATE BRIDGE							
BA	88440	450	864.1	675	864.8	760	865.0	1000	865.5
BB	89700	450	865.3	675	866.0	760	866.2	1000	866.6

^{1/} Distance in feet from downstream study limit.

U.S. DEPARTMENT OF AGRICULTURE
SOIL CONSERVATION SERVICE
PINE RIVER FLOODPLAIN MANAGEMENT STUDY
WAUSHARA COUNTY, WISCONSIN

DISCHARGE - ELEVATION DATA

PINE RIVER

TABLE 1

Flooding Source		Distance $\frac{1}{2}$	Discharge - Elevation									
Cross section	10-year		50-year		100-year		500-year		Elev. MSL			
	Q CFS		Elev. MSL	Q CFS	Elev. MSL	Q CFS	Elev. MSL	Q CFS			Elev. MSL	
<u>CARPENTER CREEK</u>												
CONFLUENCE		0	249	793.5	378	794.3	427	794.6	565	795.2		
A		1430	249	794.9	378	795.9	427	796.2	565	796.8		
B		3920	249	801.8	378	802.7	427	802.9	565	803.5		
C		3970	COUNTY	TRUNK HIGHWAY NN								
		4010	249	803.0	378	804.5	427	805.0	565	806.9		
<u>LITTLE SILVER CREEK</u>												
CONFLUENCE		0	154	787.9	218	789.0	246	789.4	315	790.2		
A		250	154	787.9	218	789.0	246	789.4	315	789.2		
B		275	COUNTY	TRUNK HIGHWAY HH								
C		315	154	788.2	218	789.0	246	789.4	315	790.2		
		3045	154	792.3	218	792.9	246	793.1	315	793.4		
D		3080	28TH STREET									
E		3125	154	792.7	218	793.1	246	793.3	315	793.6		
F		4675	154	794.4	218	794.9	246	795.2	315	795.4		
		7075	154	797.5	218	797.9	246	798.2	315	798.5		
G		7140	COUNTY	TRUNK HIGHWAY E								
		7180	154	797.9	218	798.4	246	798.6	315	798.9		
H		9110	154	801.4	218	802.0	246	802.2	315	802.8		
I		9700	154	802.3	218	802.9	246	803.1	315	803.6		

$\frac{1}{2}$ Distance in feet from confluence with Pine River.

U.S. DEPARTMENT OF AGRICULTURE
SOIL CONSERVATION SERVICE
PINE RIVER FLOODPLAIN MANAGEMENT STUDY
WAUSHARA COUNTY, WISCONSIN

DISCHARGE - ELEVATION DATA

CARPENTER AND LITTLE SILVER CREEKS

TABLE 1

Flooding Source		Discharge - Elevation									
Cross section	Distance $\frac{1}{2}$	10-year		50-year		100-year		500-year		Elev. MSL	Q CFS
		Q CFS	Elev. MSL	Q CFS	Elev. MSL	Q CFS	Elev. MSL	Q CFS	Elev. MSL		
POPPLC CRK	0	52	822.9	79	823.8	91	824.2	115	824.9		
CONFLUENCE	220	52	823.5	79	824.4	91	824.6	115	825.3		
A	250	PRIVATE DRIVEWAY									
B	285	52	824.6	79	826.6	91	827.7	115	828.3		
C	960	52	826.6	79	827.6	91	828.3	115	828.8		
D	1350	52	830.7	79	831.2	91	831.5	115	831.8		
E	1390	COUNTY TRUNK HIGHWAY A									
F	1430	52	833.3	79	834.1	91	834.5	115	835.3		
G	2230	52	839.3	79	839.9	91	840.3	115	840.7		
	2260	26TH ROAD									
	2290	52	841.1	79	841.9	91	842.2	115	842.8		

$\frac{1}{2}$ Distance in feet from confluence with Pine River.

U.S. DEPARTMENT OF AGRICULTURE
SOIL CONSERVATION SERVICE
PINE RIVER FLOODPLAIN MANAGEMENT STUDY
WAUSHARA COUNTY, WISCONSIN

DISCHARGE - ELEVATION DATA

POPPLC CRK

TABLE 1

TABLE 2
FLOODWAY DATA

FLOODING SOURCE		FLOODWAY			BASE FLOOD WATER SURFACE ELEVATION 2/			
CROSS SECTION	DISTANCE 1/	WIDTH (FEET)	SECTION AREA (SQUARE FEET)	MEAN VELOCITY (FEET PER SECOND)	WITHOUT FLOODWAY WITH DAM BREACH	WITHOUT FLOODWAY	WITH 3/ FLOODWAY AND DAM BREACH	INCREASE
PINE RIVER								
A	0	591	626	2.32	768.4	765.7	768.4	2.7
B	1920	160	700	2.10	770.2	767.4	770.2	2.8
C	3040	163	716	3.03	771.1	768.3	771.1	2.8
D	3320	177	602	2.41	771.6	768.5	771.6	3.1
E	3625	63	239	3.41	772.6	769.0	772.6	3.6
F	3780	114	672	1.21	775.1	769.8	775.1	5.3
G	3940	124	493	1.65	775.2	769.8	775.2	5.4
H	4880	191	979	1.44	778.2	775.5	778.2	3.7
I	6560	379	1397	1.01	778.2	775.6	778.2	2.6
J	8440	216	755	1.87	778.3	775.9	778.3	3.6
K	9720	369	877	1.61	778.3	776.3	778.3	2.0
L	11650	857	1548	0.89	778.5	777.1	778.5	1.4
M	15090	984	2292	0.60	780.3	779.8	780.3	0.5
N	17370	607	1951	0.70	781.3	781.1	781.3	0.2
O	20870	814	1784	0.77	783.2	783.1	783.2	0.1
P	24510	1040	2031	0.68	785.7	785.6	785.7	0.1
Q	26440	223	982	1.41	787.1	787.1	787.1	0
R	28720	250	893	1.55	789.0	789.0	789.0	0
S	29840	441	1379	0.86	789.7	789.7	789.7	0
T	29900	713	1713	0.69	789.9	789.9	789.9	0
U	30330	265	1141	1.04	790.1	790.1	790.1	0
V	32580	578	2154	0.55	790.7	790.7	790.7	0
W	35620	169	806	1.48	792.5	792.4	792.5	0.1
X	37250	426	1203	0.78	793.1	793.0	793.1	0.1
Y	40520	112	403	2.32	798.6	797.4	798.6	1.2
Z	41105	89	227	3.76	801.1	798.9	801.1	1.1

1/ DISTANCE IN FEET FROM STUDY LIMIT

2/ WATER SURFACE ELEVATION WITHOUT DEBRIS OR ICE BLOCKAGE

3/ ELEVATIONS USED FOR APPENDIX B PROFILES

U.S. DEPARTMENT OF AGRICULTURE

SOIL CONSERVATION SERVICE

WAUSHARA COUNTY FLOODPLAIN MANAGEMENT STUDY

WAUSHARA COUNTY, WISCONSIN

FLOODWAY DATA

PINE RIVER

TABLE2
FLOODWAY DATA

FLOODING SOURCE		FLOODWAY			BASE FLOOD WATER SURFACE ELEVATION 2/			
CROSS SECTION	DISTANCE 1/	WIDTH (FEET)	SECTION AREA (SQUARE FEET)	MEAN VELOCITY (FEET PER SECOND)	WITHOUT FLOODWAY WITH DAM BREAK	WITHOUT FLOODWAY	WITH FLOODWAY AND DAM BREACH	INCREASE
PINE RIVER CONT.								
AA	41315	37	155	5.50	805.3	800.1	805.3	5.2
AB	42525	81	307	3.05	809.2	808.0	809.2	1.2
AC	43845	256	436	2.15	810.6	810.0	810.6	0.6
AD	47295	387	766	1.22	814.7	814.6	814.7	0.1
AE	51275	285	953	0.98	817.7	817.7	817.7	0
AF	53915	524	1406	0.67	818.3	818.3	818.3	0
AG	57295	425	1036	0.90	820.2	820.2	820.2	0
AH	57315	410	554	1.69	820.4	820.4	820.4	0
AI	60650	463	856	1.09	822.7	822.3	822.7	0.4
AJ	62950	133	434	2.15	825.2	824.2	825.2	1.0
AK	64050	226	579	1.46	826.4	824.9	826.4	1.5
AL	64115	78	374	2.26	826.5	825.1	826.5	1.4
AM	66215	87	322	2.62	826.7	826.7	826.7	0
AN	67300	679	1143	0.74	835.3	835.3	835.3	0
AO	68700	277	600	1.41	835.5	835.5	835.5	0
AP	70100	62	245	3.45	837.4	837.4	837.4	0
AQ	70185	100	423	2.00	839.3	839.3	839.3	0
AR	71345	159	242	3.49	848.1	848.1	848.1	0
AS	72065	79	227	3.73	850.8	850.8	850.8	0
AT	72155	237	498	1.70	852.4	852.4	852.4	0
AU	72955	328	372	2.27	853.7	853.7	853.7	0
AV	73030	333	677	1.25	854.6	854.6	854.6	0
AW	73630	373	648	1.30	855.5	855.5	855.5	0
AX	74950	568	1135	0.71	857.0	857.0	857.0	0
AY	82190	790	1425	0.56	860.8	860.8	860.8	0
AZ	88400	843	1529	0.50	864.9	864.4	864.9	0.5

1/ DISTANCE IN FEET FROM STUDY LIMIT

2/ WATER SURFACE ELEVATION WITHOUT DEBRIS OR ICE BLOCKAGE

U.S. DEPARTMENT OF AGRICULTURE

SOIL CONSERVATION SERVICE

WAUSHARA COUNTY FLOODPLAIN MANAGEMENT STUDY

WAUSHARA COUNTY, WISCONSIN

FLOODWAY DATA

PINE RIVER

TABLE 2
FLOODWAY DATA

FLOODING SOURCE		FLOODWAY			BASE FLOOD WATER SURFACE ELEVATION 2/			
CROSS SECTION	DISTANCE 1/	WIDTH (FEET)	SECTION AREA (SQUARE FEET)	MEAN VELOCITY (FEET PER SECOND)	WITHOUT FLOODWAY WITH DAM BREAK	WITHOUT FLOODWAY	WITH 4/ FLOODWAY AND DAM BREACH	INCREASE
PINE RIVER CONT.								
BA	88440	868	1674	0.45	685.1	865.0	865.1	0.1
BB	89700	1000	1905	0.40	866.2	866.2	866.2	0
CARPENTER CREEK 3/								
A	1430	249	689	0.62	796.2	796.2	796.2	0
B	3920	219	410	1.04	802.9	802.9	802.9	0
C	4010	284	1129	0.38	805.0	805.0	805.0	0
LITTLE SILVER CREEK 3/								
A	250	294	1185	0.21	789.4	789.4	789.4	0
B	315	283	1093	0.23	789.4	789.4	789.4	0
C	3045	337	797	0.31	793.1	793.1	793.1	0
D	3125	256	872	0.28	793.3	793.3	793.3	0
E	4675	252	602	0.41	795.2	795.2	795.2	0
F	7075	268	535	0.46	798.2	798.2	798.2	0
G	7180	257	671	0.37	798.6	798.6	798.6	0
H	9110	179	387	0.64	802.2	802.2	802.2	0
I	9700	230	458	0.54	803.1	803.1	803.1	0

1/ DISTANCE IN FEET FROM STUDY LIMIT

4/ ELEVATIONS USED FOR APPENDIX B PROFILES

2/ WATER SURFACE ELEVATION WITHOUT DEBRIS OR ICE BLOCKAGE

3/ DISTANCE IN FEET FROM CONFLUENCE WITH PINE RIVER

U.S. DEPARTMENT OF AGRICULTURE

FLOODWAY DATA

SOIL CONSERVATION SERVICE

WAUSHARA COUNTY FLOODPLAIN MANAGEMENT STUDY

PINE RIVER, CARPENTER CREEK, LITTLE SILVER CREEK

WAUSHARA COUNTY, WISCONSIN

TABLE2
FLOODWAY DATA

FLOODING SOURCE		FLOODWAY			BASE FLOOD WATER SURFACE ELEVATION 2/			
CROSS SECTION	DISTANCE 1/	WIDTH (FEET)	SECTION AREA (SQUARE FEET)	MEAN VELOCITY (FEET PER SECOND)	WITHOUT FLOODWAY WITH DAM BREACH	WITHOUT FLOODWAY	WITH 3/ FLOODWAY AND DAM BREACH	INCREASE
POPPLE CREEK								
A	220	106	90	1.01	824.6	824.6	824.6	0
B	285	137	422	0.22	827.7	827.7	827.7	0
C	960	72	115	0.79	828.3	828.3	828.3	0
D	1350	20	35	2.61	831.5	831.5	831.5	0
E	1430	134	173	0.53	834.5	834.5	834.5	0
F	2230	30	43	2.11	840.3	840.3	840.3	0
G	2290	54	109	0.84	842.2	842.2	842.2	0

1/ DISTANCE IN FEET FROM STUDY LIMIT
2/ WATER SURFACE ELEVATION WITHOUT DEBRIS OR ICE BLOCKAGE
3/ ELEVATIONS USED FOR APPENDIX B PROFILES

U.S DEPARTMENT OF AGRICULTURE
SOIL CONSERVATION SERVICE
WAUSHARA COUNTY FLOODPLAIN MANAGEMENT STUDY
WAUSHARA COUNTY, WISCONSIN

FLOODWAY DATA

POPPLE CREEK

Appendix F

INVESTIGATIONS AND ANALYSIS

Investigation and Analysis

The Pine River watershed is a relatively flat watershed with many kettle depressional areas, swamps and depressional lakes. The soils are sandy and rapidly permeable. Of the 99.4 square miles of drainage area only 70.3 square miles directly contribute to surface runoff. The remainder of the drainage area would drain to the water table and appear as prolonged stream flow or base flow. The base flow is estimated to range from 65 to 100 cfs. Due to the nature of the watershed a single storm event model would not produce a reasonable floodflow. Using runoff only would not be realistic because it would be difficult to predict the amount of frozen ground. Sands, especially high water table sands, would not be frozen solid under a snow pack, therefore it is difficult to predict the amount that would infiltrate or runoff. The 100-year March snowpack is eight inches of water equivalent, which would cause a major flood given a fast melt on frozen ground. The USGS regression formula approach gives a more realistic floodflow (1). This approach is based on the historical gage records of streams grouped in areas of similar topography.

The resultant flows used in the study are listed for each cross section and frequency in Appendix A.

The flows and surveyed cross section data were modeled in a step backwater computer program (3). The resultant water surface elevations for each cross section are listed in Appendix E and the profiles are shown in Appendix B.

The floodplain, floodway limits, and cross section locations are shown on photomaps in Appendix A.

The outflow of the Saxville spillway during the July 1969 event should equal or exceed the regional flood flow, which would require removing all of the stoplog/panels from the spillway, to keep the water from overtopping the dam. A downstream landowner indicated the approximate flood level during the 1969 event. The landowner was awakened by the sound of the water rushing by his residence. The flood level correlated favorably with the computed regional (100-yr) flood profile of this report.

The 100-year flood elevations are based on the assumption the outlet structures for the Pine River and Poy Sippi Dams are operational and the Saxville Dam has only the top panels removed.

The three dams in the study area, Saxville, Pine River and Poy Sippi were breached utilizing the National Weather Service Dam Break Flood Forecasting Model (DAMBRK)(9) The worst case scenario, no one able to operate the spillways (stoplogs could not be removed) causing the dams to overtop and fail, was used in the model. The failure flood was routed until the floodwaters receded to the regional (100-yr) flood level then terminated. The results are shown on the photomaps in Appendix A, the profiles of Appendix B, and the tables of Appendix E.

Appendix G

GLOSSARY

GLOSSARY

CHAPTER NR. 116, WISCONSIN'S FLOODPLAIN MANAGEMENT PROGRAM NR. 116.03 DEFINITIONS

Channel. A channel is a natural or artificial watercourse with definite bed and banks to confine and conduct the normal flow of water.

Department. Department refers to the State of Wisconsin Department of Natural Resources.

Encroachment. An encroachment is any fill, structure, building, use, accessory use, or development in the floodway.

Encroachment/Floodway Lines. Encroachment/floodway lines are limits of obstruction to floodflows. These lines are on both sides of and generally parallel to the river or stream. The lines are established by assuming that the area landward (outside) of the encroachment/floodway lines will be ultimately developed in such a way that it will not be available to convey floodflows.

Flood. A general and temporary condition of partial or complete inundation of normally dry land areas caused by the overflow or rise of rivers, streams, or lakes.

Flood Frequency. The term flood frequency is a means of expressing the probability of flood occurrences and is generally determined from statistical analyses. The frequency of a particular floodflow is usually expressed as occurring, on the average, once in a specified number of years. Any particular floodflow could, however, occur more frequently than once in any given year.

Flood Fringe. The flood fringe is that portion of the floodplain outside of the floodway, which is covered by floodwaters during the regional flood; it is generally associated with standing water rather than rapidly flowing water.

Floodplain. The floodplain is the land which has been or may be hereafter covered by floodwater during the regional flood. The floodplain includes the floodway and the flood fringe.

Floodplain Management. Floodplain management involves the full range of public policy and action for insuring wise use of floodplains. It includes everything from the collection and dissemination of flood control information to actual acquisition of floodplain lands; and the enactment and administration of codes, ordinances, and statutes for land use in the floodplain.

Flood Proofing. Flood proofing involves any combination of structural provisions, changes, or adjustments to properties and structures subject to flooding, primarily for the purpose of reducing or eliminating flood damage to properties, water and sanitary facilities, structures and contents of buildings in flood hazard areas.

Flood Protection Elevation. The flood protection elevation shall correspond to a point 2 feet of freeboard above the water surface profile associated with the regional flood and the official floodway lines. Also see: Freeboard.

Floodway. The floodway is the channel of a river or stream and those portions of the floodplain adjoining the channel required to carry and discharge the floodwater or floodflows associated with the regional flood.

Freeboard. Freeboard is a factor of safety usually expressed in terms of a certain amount of feet above a calculated flood level. Freeboard compensates for the many unknown factors that contribute to flood heights greater than the height calculated. These unknown factors include, but are not limited to, ice jams, debris accumulation, wave action, obstruction of bridge openings and floodways, the effects of urbanization on the hydrology of the watershed, loss of flood storage areas due to development and aggradation of the river or streambed.

High Flood Damage Potential. High flood damage potential is associated with any danger to life or health and any significant economic loss to a structure or building or its contents.

Hydraulic Floodway Lines. Hydraulic floodway lines shall delineate the channel of the river or stream and those portions of the adjoining floodplains which are reasonably required to carry and discharge the regional floodflow without any measurable increase in flood heights.

Hydraulic Reach. A hydraulic reach along a river or stream is that portion of the river or stream extending from one significant change in the hydraulic character of the river or stream to the next significant change. These changes are usually associated with breaks in the slope of the water surface profile, and may be caused by bridges, dams, expansion and contraction of the waterflow, and changes in streambed slope or vegetation.

Levee. A levee is a continuous dike or embankment of earth constructed parallel to a river or stream to prevent flooding of certain areas of land.


Official Floodway Lines. Official floodway lines are those lines which have been adopted by the county, city, or village, approved by the department, and which are shown on the official floodplain zoning maps and used for regulatory purposes.

Regional Flood. The regional flood is a flood determined to be representative of large floods known to have generally occurred in Wisconsin and which may be expected to occur on a particular stream because of like physical characteristics. The regional flood is based upon a statistical analysis of streamflow records available for the watershed and/or an analysis of rainfall and runoff characteristics in the general watershed region. The flood frequency of the regional flood is once in every 100 years; this means that in any given year there is a 1 percent chance that the regional flood may occur. During a typical 30-year mortgage period, the regional flood has a 26 percent chance of occurring.

Structure. A structure is any manmade object with form, shape, and utility, either permanently or temporarily attached to or placed upon the ground, riverbed, streambed, or lakebed.

Watershed. A watershed is a region or area contributing ultimately to the water supply of a particular watercourse or body of water.

Water Surface Profile. The water surface profile is a graphical representation of the height of the water surface throughout a county, city, or village based upon a certain flow passing through the river or stream. A water surface profile based upon flows occurring during a regional flood is used in regulating the floodplain areas.



Appendix H

BIBLIOGRAPHY

Bibliography and Related References

1. Conger, Duane H., Techniques for Estimating Magnitude and Frequency of Floods for Wisconsin Streams, U.S. Department of the Interior, Geological Survey, Water Resources Division, Madison, Wisconsin, 1981.
2. State of Wisconsin, Blue Book, Wisconsin Legislative Reference Bureau, 1975.
3. USDA Soil Conservation Service, Engineering Division, Technical Release No. 61, WSP2 Computer Program May 1976, Rev. 9/1/82.
4. Wisconsin's Floodplain Management Program, Wisconsin Administrative Code NR116, Department of Natural Resources.
5. Shaw & Fredine, 1956. Wetlands of the United States. United States Department of Interior, Fish and Wildlife Service, Circular 39, 67 pages.
6. Interagency Advisory Committee on Water Data. Guidelines for Determining Flood Flow Frequency, Bulletin #17B, March 1982, U.S. Department of the Interior Geological Survey, Office of Water Data Coordination.
7. U.S. Department of Commerce Weather Bureau. Frequency of Maximum Water Equivalent of March Snow Cover in North Central United States. Technical Paper No. 50, Washington DC, 1964.
8. U.S. Department of Commerce, National Oceanic and Atmospheric Administration. Climates of the States, Volume 1-Eastern States 1974. A Water Information Center Publication.
9. U.S. Department of Commerce, NOAA National Weather Service, DAMBRK, The Dam-Break Flood Forecasting Model, Office of Hydrology, National Weather Service (NWS), Silver Spring, Maryland, 20910 July 18, 1984.

NATIONAL AGRICULTURAL LIBRARY



1022269712

9



1022269712

